

## Drynam Heath Quiet Street, Kinsealy Stage 1 Road Safety Audit

Fingal County Council

March 2025

## Drynam Heath Quiet Street, Kinsealy

## Stage 1 Road Safety Audit

March 2025

#### Notice

This document and its contents have been prepared and are intended solely for Fingal County Council's information and use in relation to Drynam Heath Quiet Street, Kinsealy.

Traffico assumes no responsibility to any other party in respect of or arising out of or in connection with this document and / or its contents.

#### **Document History**

JOB NUMBER: 250016			DOCUMENT REF: 250014RPT001_RSA1_Rev_1			
1	Final Issue	MD	MD	MD	MD	21 Mar. 2025
0	Draft Issue	MD	MD	СР	MD	27 Feb 2025
Revision	Purpose Description	Originated	Checked	Reviewed	Authorised	Date

## Contents

Sec	ction	Page
1.	Introduction	2
1.1	Report Context	2
1.2	Details of Site Inspection	2
1.3	The Road Safety Audit Team	2
1.4	Design Drawings Examined as Part of the Audit Process	2
1.5	Road Safety Audit Compliance	2
2.	Road Safety Issues Identified	4
2.1	Problem: Missing Cul de Sac Signs	4
2.2	Problem: Pedestrian Strikes on Traffic Bollards	4
2.3	Problem: Existing Junction Ahead Warning Signs	5
3.	Audit Team Statement	6
3.1	Certification & Purpose	6
3.2	Implementation of RSA Recommendations	6
3.3	Road Safety Audit Team Sign-Off	6
4.	Designers Response	7
4.1	How the Designer Should Respond to the Road Safety Audit	7
4.2	Returning the Completed Feedback Form	7
List o	of Tables	
Table	e 1.1 – Site Inspection Details	2
Table	e 1.2 – Audit Team Details	2
Table	e 1.3 – Designers Drawing List	2

#### List of Figures Figure 2.1 – Location Where Suitable Signs & Lines Should Be Provided Highlighting Cul de Sac Figure 2.2 – Indicative Bollards Alignment on Feltrim Road Leading to Pedestrian Strikes Figure 2.3 – Junction Ahead Warning Signs Causing Confusion for Drivers Figure 4.1 – Road Safety Audit Sign-Off and Completion Process

### Appendices

Append	dix A	8
A.1	Road Safety Audit Feedback Form	8

4

4

5 7

## 1. Introduction

### 1.1 Report Context

This report describes the findings of a Stage 1 Road Safety Audit associated with the Drynam Heath Quiet Street, Kinsealy.

The Audit has been completed by Traffico on behalf of Fingal County Council.

### 1.2 Details of Site Inspection

Date	Daylight / Darkness	Weather & Road Conditions
Wednesday 26th February 2025	Daylight	Sunny with dry road pavements.

Table 1.1 – Site Inspection Details

### 1.3 The Road Safety Audit Team

The members of the Road Safety Audit Team have been listed following:

Status	Name / Qualifications	TII Auditor Reference No:
Audit Team Leader (ATL)	Martin Deegan BEng(Hons) MSc CEng MIEI	MD101312
Audit Team Member (ATM)	Colin Prendeville BEng(Hons) CEng MIEI	CP3369500

Table 1.2 – Audit Team Details

### 1.4 Design Drawings Examined as Part of the Audit Process

The following drawing was examined as part of the Road Safety Audit (RSA) process:

Drawing No.	Drawing Title	Revision
KQS-FCC-03-S1	Drynam Heath, Kinsealy G.A. Option 3 & Details	P03

Table 1.3 – Designers Drawing List

### 1.5 Road Safety Audit Compliance

#### **Procedure and Scope**

This Road Safety Audit has been carried out in accordance with the procedures and scope set out in TII publication number GE-STY-01024 - Road Safety Audit.

As part of the road safety audit process, the Audit Team have examined only those issues within the design which relate directly to road safety.

#### **Compliance with Design Standards**

The road safety audit process is not a design check, therefore verification or compliance with design standards has not formed part of the audit process.

#### **Minimizing Risk of Collision Occurrence**

All problems described in this report are considered by the Audit Team to require action in order to improve the safety of the scheme and minimise the risk of collision occurrence.

## 2. Road Safety Issues Identified

### 2.1 Problem: Missing Cul de Sac Signs

#### Location: Junction of Drynam Heath & Drynam Green

Failing to alert incoming drivers that Drynam Heath is not a through-as road could lead to sudden braking on approach to the bollards and extended (risky) reversing manoeuvres.

Figure 2.1 – Location Where Suitable Signs & Lines Should Be Provided Highlighting Cul de Sac



#### Recommendation

Suitable signage should be provided at the entry point to Drynam Heath to inform drivers that the street operates as a Cul de Sac.

### 2.2 Problem: Pedestrian Strikes on Traffic Bollards

#### Location: Pedestrian Crossing at Junction of Drynam Heath & Feltrim Road

The proposed alignment of the bollards could lead to pedestrian strikes and progression issues for mobility impaired road users (especially the blind or partially sighted) wishing to access the courtesy crossing.



Figure 2.2 – Indicative Bollards Alignment on Feltrim Road Leading to Pedestrian Strikes

#### Recommendation


The position of the bollards should be adjusted to facilitate universal access to the courtesy crossing (i.e. especially mobility impaired pedestrians).

### 2.3 Problem: Existing Junction Ahead Warning Signs

#### Location: Feltrim Road – Northbound & Southbound Approaches to Drynam Heath

The existing junction ahead warning signs could lead to driver confusion and vehicle strikes on the bollards. Especially during low light conditions.

Figure 2.3 – Junction Ahead Warning Signs Causing Confusion for Drivers



#### Recommendation

The junction ahead warning signs should be removed, and the traffic bollards should be fitted with suitable reflectors.

## 3. Audit Team Statement

### 3.1 Certification & Purpose

We certify that we have examined the drawing(s) listed in Chapter 1 of this Report.

#### Sole Purpose of the Road Safety Audit

The Road Safety Audit has been carried out with the sole purpose of identifying any features of the design which could be removed or modified to improve the road safety aspects of the scheme.

### 3.2 Implementation of RSA Recommendations

The problems identified herein have been noted in the Report together with their associated recommendations for road safety improvements.

We (the Audit Team) propose that these recommendations should be studied with a view to implementation.

#### Audit Team's Independence to the Design Process

No member of the Audit Team has been otherwise involved with the design of the measures audited.

### 3.3 Road Safety Audit Team Sign-Off

**Martin Deegan** 

Audit Team Leader Road Safety Engineering Team **traffico**  Signed:

Nat leg

27<sup>th</sup> February 2025

#### **Colin Prendiville**

Audit Team Member Road Safety Engineering Team traffico Signed:

Date:

Date:

Colin Rencleville

27th February 2025

## 4. Designers Response

### 4.1 How the Designer Should Respond to the Road Safety Audit

The Designer should prepare an Audit Response for each of the recommendations using the Road Safety Audit Feedback Form attached in Appendix A.

When completed, this form should be signed by the Designer and returned to the Audit Team for consideration. See flow-chart following for further description.



Figure 4.1 – Road Safety Audit Sign-Off and Completion Process

### 4.2 Returning the Completed Feedback Form

The Designer should return the completed Road Safety Audit Feedback Form attached in Appendix A of this report to the following email address:

- Email address: <u>martin@traffico.ie</u>
- Telephone: 01 699 1551

The Audit Team will consider the Designer's response and reply indicating acceptance or otherwise of the Designers response to each recommendation.

#### **Triggering the Need for an Exception Report**

Where the Designer and the Audit Team cannot agree on an appropriate means of addressing an underlying safety issue identified as part of the audit process, an Exception Report must be prepared by the Designer on each disputed item listed in the audit report.

## Appendix A

A.1 Road Safety Audit Feedback Form

## **Road Safety Audit Feedback Form**

Scheme: Drynam Heath Quiet Street, Kinsealy

Audit Stage: Stage 1 Road Safety Audit

Audit Date: 27th February 2025

Problem Reference (Section 2)	Designer Response Section			Audit Team Response Section
	Problem Accepted ( yes / no )	Recommended Measure Accepted ( yes / no )	Alternative Measures or Comments	Alternative Measures Accepted ( yes / no )
2.1	Yes	Yes	Recommendation Accepted	
2.2	Yes	Yes	Recommendation Accepted	
2.3	Yeş	Yes	Recommendation Accepted	

\*The Designer should complete the Designer Response Section above, then fill out the designer details below and return the completed form to the Road Safety Audit Team for consideration and signing.

Designer's Name:	Larry Bergin	Designer's Signature:	, Date:	5/3/2025
Employer's Name:	Larry Bergin	Employer's Signature:	Date:	5 / 3 / 2025
Audit Team's Name:	Martin Deegan	Audit Team's Signature:	Date:	21/03/2025



1

2.1

19/11

In

۲

302

5.5

5----

MANP.

198 - 9 Mar

14.

Ē

N THE ALE

1R

ł

Airport Express Station 發唱快援范

九日 Kowloon (W) ←九星(西) ← 10000 (W)

37

意場快發站